


15-127-19018-0000

Form CP-3
Rev. 6-26-62



KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION

FEB 5 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rosen & Schriener ^{Schriener}

Complete Address: 701 Union Center Bldg, Wichita Kansas.

Lease Name Grass Well No. 4

Location SE-SE-SE Sec. 35 Twp. 16 Rge. 5 (E) (W)

County Morris Total Depth 2241'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304 Chase Kansas. License No. 436

Operation Completed: Hour 6:PM Day 30 Month I Year 1963

The Above well was plugged as follows:

Filled hole w/ sand from T.O. 2241' back to 2185' ran 5 sax cement w/ dump bailer.
Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 2150' back to 155' set a
10' rock bridge and ran 20 sax cement. Filled hole w/ mud from 85' back to 30' set a
5' rock bridge and ran 8 sax cement from 25' back to zero. 8 5/8" surface pipe 3'
below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2-5-63
INV. NO. 7020-E