

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 2-52 Location: NW NW SE 15-051-04153-00-01

County: Ellis Sec. 4 Twp. 10 Rge. 17 (E) (W)

Name of Field or Pool: _____ Total Depth: 5809

I have this date completed supervision of plugging of:

Well No. 1 SWD Lease Walters

Operator's Full Name The Texas Co

Complete Address: 614 Bitting Bldg Wichita, Kans

Plugging Contractor: ~~Wichita, Kansas~~ Arnett Pipe Pulling Co

Address: Hoisington, Kans License No. 205

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 12 Noon Day 9 Month 12 Year 58

The above well was plugged as follows:

8 5/8" at 150' circulated with cement - 5 1/2" 5586' - 4" liner 5550' to 5655'
2" tubing lost in hole - top of tubing at 704'.

Started 700' 5 1/2", circulated hole with heavy mud through 5 1/2" at 700',
(52 sax Gel), displaced 20 sax cement through 5 1/2' at 500', heavy mud to
125', displaced 20 sax cement through 5 1/2" at 125', heavy mud to 40',
set rock bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Jewel M. Ogden*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1958

CONSERVATION DIVISION
Wichita, Kansas

Reviewed: *J. Lewis Brock*
Field Supervisor

Signed: _____
Well Plugging Supervisor

Remarks:

PLUGGING
FILE SEC 4 T. 13 R. 17W
BOOK PAGE 2 LINE 32