

15-051-19279-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JAN 26 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Sohio Petroleum Company
Complete Address: Box 673 Russell, Kansas
Lease Name Henderson "F" Well No. 1
Location NW SW SW Sec. 22 Twp. 11 Rge. 18 (E) (W) X
County Ellis Total Depth 3505
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____
Plugging Contractor: Co. Tools by Howco
Address: Hays, Kansas License No. _____
Operation Completed: Hour 12:30 P Day 13 Month 1 Year 1967

The Above well was plugged as follows:

Total Depth 3505' 8 5/8 csg set at 142' cwc.
5 1/2 csg set at 3496' cw 150 sc cement.
Perf. (3345-52) (3219-29) 3110-18) Dakato squeezed-Dakato leak at time of abandonment.
PB 3478' Filled with rock and gravel to 3354' Dumped 5 sc cem. with dump bailer.
Set bridge at 950' filled with rock to 870' dumped 3 sc calseal with dump bailer.
Squeezed 5 1/2 csg with 5 sc gel and 80 sc cement. Shut in pres. 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: K. M. Massey
Well Plugging Supervisor

INVOICED
DATE 1/16/67
INV. NO. 4610-W