

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
15:05:205/2:00:00
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name Ehtel M. Witt Well No. 1 - V

Location NW NW SE Sec. 23 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3735

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas 67530 License No. 637

Operation Completed: Hour 12 N Day 28 Month 10 Year 1970

The above well was plugged as follows:

Total Depth 3735' 8 5/8 csg set at 565' cwc 300 sk.

4 1/2 csg set at 3734' cw 175 sk cmt.

4 1/2 csg PBTD 3730' with top perf. 3521'.

Filled 4 1/2 csg w/sd (3500-3730) Dumped 4 sk cmt w/dump bailer. (3460-3500)

Cutoff and recovered 2625' of 4 1/2 csg.

Set rock and sand bridge at 500' - Dumped 5 sk cmt W/dump bailer.

Balcd hole dry and dumped 6 1/2 yds readymix cmt (0-500)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 10-30-70

INV. NO. 2782-W