

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1982
4:26-82

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051 -21,465-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Dreiling Oil, Inc.

Complete Address R.R. #1 Victoria, Ks. 67671

Lease Name Leiker Well No. #3

Location C of N/2 SW NE Sec. 23 Twp. 13 Rge. 18 (East) (West)

County Ellis Total Depth 3788'

Abandoned Oil Well XXXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dreiling Oil, Inc.

Address R.R. #1 Victoria, Ks. 67671 License No.

Operation Completed: Hour: 1:30 PM Day: 20 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All XXXXX Part None

The above well was plugged as follows:

8 5/8"-167' S.P. cnc w/130 sacks common. 4 1/2" casing set @ 3787' w/200 sacks
common. Top perf. at 3470'. Pushed plug to 3450' w/50' of sand & 5 sacks cement
on top. Shot pipe 1 time & recovered 960'. Ordered 140 sacks 50/50 posmix-4% Gel.
3% Cal.Cl., 19 sacks Gel., 5 sacks hulls & 8 5/8" plug. Pumped into S.P. w/pump
truck, 4 sacks hulls, 15 sacks Gel., 70 sacks cement, 4 sacks Gel., 1 sack hulls
released plug & followed w/70 sacks cement. Maximum Pressure 500 pounds

Amount of Surface Casing: 167' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

INDEXED
4-27-81
9981-W