

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1982
4-26-82

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051 -21,771-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Dreiling Oil, Inc.

Complete Address R.R. #1 Victoria, Ks. 67671

Lease Name Leiker Well No. 4

Location 990' FSL & 270' FWL NE/4 Sec. 23 Twp. 13 Rge. 18 (East) (West)

County Ellis Total Depth 3735'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dreiling Oil, Inc.

Address R.R.#1 Victoria, Ks. 67671 License No.

Operation Completed: Hour: 3:00 PM Day: 20 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All XXX Part None

The above well was plugged as follows:

8 5/8"-167' S.P. Cuc. w/125 sacks common, 4 1/2" casing set @ 3610' w/ 150 sacks
common. Top perf. @ 3475'. Sand bottom w/sand & 5 sacks cement to 3400'.
Shot pipe 1 time & recovered 1050'. Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.
19 sacks Gel., 5 sacks hulls & 8 5/8" plug. Pumped into S.P. w/pump truck, 4
sacks hulls, 15 sacks Gel., 70 sacks cement, 4 sacks Gel., 1 sack hulls, released
8 5/8" plug & followed w/ 70 sacks cement. Maximum Pressure 400 pounds.

Amount of Surface Casing: 167' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

INVOICED

DATE 4-27-82
INV. NO. 9982-4