

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1974
2-12-74
CONSERVATION DIVISION
Wichita, Kansas

15:051-20936:00:00

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Building, Russell, Kansas

Lease Name Fellers "B" Well No. 1

Location SE SE SE Sec. 9 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3490'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Teels

Address License No.

Operation Completed: Hour 5:15 P Day 8 Month 2 Year 1974

The above well was plugged as follows:

RTD 3490' 8 5/8 esg set at 282' ewe 150 sk.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk
ent thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Marney
Well Plugging Supervisor

INVOICED

DATE 2/12/74

INV. NO. 8563-W