

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-051-04413-00-00

FILE NO. _____

LOCATION NE NE SW

SEC. 28 TWP. 13 RGE. 17

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-C Lease _____ Drilling _____

Operator Joe Mischner Address Russell, Kans

Field _____ County Ellis

Total Depth 3541 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 140' circulated with cement- 4 1/2" 3404 with
150 sax cement behind, top perf 3202', filled with chat
to 3200', set 5 sax cement with dump bailer, pulled
2050', 4 1/2", mudded hole to 125', set rock bridge and 15
sax cement, filled with mud to 35', set rock and 10 sax
cement to bottom cellar.

PLUGGING
FILE SEC. 28 T. 13 R. 17W
BOOK PAGE 27 LINE 28

9-12-50
[Signature]
District Conservation Agent

Date 9-8-50