

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-051-06755-00-00

FILE NO. 21-45

LOCATION NW NW SE

SEC. 28 TWP. 13 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-B Lease Dreiling

Operator Natl Pet Reserve Corp Address R. H. Ernest Shirkmere Wichita,

Field _____ County Ellis

Total Depth 3334 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 118' circulated with cement.
5 1/2" at 3326' cemented in, squeezed with cement at
610' drilled out to bottom. Hole filled with chat to
3314' run 6 sax cement with dump bailer, pumped hole
full prepared mud, pumped cementing plug to 570' followed
by 50 sax cement squeezed through 570' hole in 5 1/2', left
cement in hole and top plug at 400', filled with prepared
mud to 60', set wood plug and filled hole to 10' with cement,
filled from 10' to 0' with earth.

Cementing by Accuracy Co 9-6-50

PLUGGING
FILE SEC 28 T 13 R 17 W
BOOK PAGE 21 LINE 45

[Signature]
District Conservation Agent

Date 9-5-50