

12

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
8-14-78  
AUG 14 1978  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 051- 21,526 - 0000 (for CHS well)

Operator's Full Name D-G Oil Operations

Complete Address Box 503, Hays, Kansas

Lease Name Dreiling Well No. 1

Location 190' S NE SE NE Sec. 28 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3541'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Western Petro.

Address Colby, Kansas License No.     

Operation Completed: Hour 2:30 P Day 11 Month 8 Year 1978

The above well was plugged as follows:

RTD 3541' 8 5/8 csg set 146' cwc 125 sk. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 150' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 8-17-78  
INV. NO. 7848.6