

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5004  
Name: Vincent Oil Corporation  
Address 1: 155 N. Market, Ste 700  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67202 + 1821  
Contact Person: M.L. Korphage  
Phone: ( 316 ) 262-3573  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 5420  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 057-20700-00-00  
Spot Description: SE-NE-NE-NW  
-SE NE NE NW Sec. 36 Twp. 28 S. R. 23  East  West  
650 Feet from  North /  South Line of Section  
2,350 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ford  
Lease Name: McCarty Well #: 2-36  
Date Well Completed: 10/25/2010  
The plugging proposal was approved on: 10/25/2010 (Date)  
by: Mr. Jerry Stapleton (KCC District Agent's Name)  
Plugging Commenced: 10/25/2010  
Plugging Completed: 10/25/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface Casing	8 5/8"	654'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Drill hole filled with heavy rotary mud and cement plugs set through drill pipe as follows:  
50 sx plug set @ 1530', 50 sx plug set @ 690', 40 sx plug set @ 300', and 20 sx plug @ 60' to surface.  
Plugged rathole with 30 sx and mousehole with 20 sx.  
Used a total of 210 sx 60 /40 POZ (4% Gel), Cementing by Allied Cementing Co. LLC. Ticket # 30838.  
Plug down at 7:00 PM 10/25/2010

Plugging Contractor License #: 5929 Name: Duke Drilling Co. Inc.  
Address 1: P.O. Box 823 Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530 + \_\_\_\_\_  
Phone: ( 620 ) 793-8366  
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation  
State of Kansas County, Sedgwick, ss.  
M.L. Korphage  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M.L. Korphage DL