

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 33530 Name: Reif Oil and Gas Company, LLC Address 1: PO Box 298 Address 2: City: Hoisington State: KS Zip: 67544 Contact Person: Don Reif Phone: (620) 786-5698 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 009-2530-00-00 Spot Description: SW NE SW Sec. 34 Twp. 16 S. R. 15 East West 1,480 Feet from North South Line of Section 1,965 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barton Lease Name: J. Steinert Well #: 1 Date Well Completed: 3/29/2011 The plugging proposal was approved on: 3/25/2011 (Date) by: David Wann (KCC District Agent's Name) Plugging Commenced: 3/29/2011 Plugging Completed: 3/29/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8", 521', 0'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 190 sacks 60/40 Poz, 4% gel, 1/4# flo seal per sack, 1st plug @ 3532' with 25 sacks, 2nd plug @ 1034' with 25 sacks, 3rd plug @ 570' with 100 sacks, 4th plug @ 40' to surface with 10 sacks, 30 sacks for rat hole, Plug down @ 3:30 pm on 3/29/2011, cement did circulate. Quality (Ticket #4742).

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc. Address 1: PO Box 276 Address 2: City: Ellinwood State: Kansas Zip: 67526 Phone: (620) 564-3800

RECEIVED APR 06 2011

KCC WICHITA

Name of Party Responsible for Plugging Fees: Reif Oil and Gas Company, LLC State of Kansas County, Barton, ss. Jennifer Heape (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jennifer Heape

Handwritten initials 'JH'

SOUTHWIND DRILLING, INC.
PLUGGING ORDERS AND REPORTS

Lease: J Steinert

Plugging received from KCC representative:

Name: David Wann Date 3-25-11 Time 9:00 A.M.

1st plug @ 3532 ft. 25 sx. Stands: 56 1/2

2nd plug @ 1034 ft. 25 sx. Stands: 16 1/2

3rd plug @ 570 ft. 100 sx. Stands: 9

4th plug @ 40 ft. 10 sx. Stands: 1

5th plug @ — ft. — sx. Stands: —

Mousehole — sx.

Rahole 30 sx.

Total Cement used: 190 sx.

Type of cement 60/40 4% gel 1/4th Flo Seal Per Sx

Plug down @ 3:30 p.m. 3-29-11

Call KCC When Completed:

Name: Case Morris Date 3-30-11 Time 10:55 A.M.

RECEIVED
APR 06 2011
KCC WICHITA