

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30553
Name: Unrein Oil Co.
Address 1: 300 W. 40th ST.
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Gelnn Unrein
Phone: (785) 628-6231
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Abuckle Depth to Top: 3639 Bottom: 3641 T.D. 3641
L/KC Depth to Top: 3403 Bottom: 3470 T.D. 3470
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - -051-02459-00-00
Spot Description: SE/4
C W/2 NE SE Sec. 11 Twp. 12 S. R. 18 East West
1,980 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Colorado-Koerner Well #: 1
Date Well Completed: 1950
The plugging proposal was approved on: 12/20/2010 (Date)
by: Rich Williams (KCC District Agent's Name)
Plugging Commenced: 12/29/10
Plugging Completed: 1/21/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
L/KC	lime stone	good	8 5/8"	1378	none
ARB	Dol.	good	5 1/2"	3640	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

12/29/10 Perforated 1350', 2 holes, Ran in tubing tagged junk at 3450', pulled up to 3360', Quality Oil Well Cementing pumped 13 sxs gel followed with 50 sks cement, pulled tubing to 1605', pumped 175 sks with 350 # hulls, Pulled tubing OOH, tied on to casing, pumped 325 sxs, waited 1.5 HRS. pumped 200 sxs, good circulation but no cement, shut in. Cut off 5 1/2" and 8 5/8" casing, ran wire line, cement at 200' both sides, 1/19/11, topped off casing with 2 yards of cement redi mix, not full, 1/21/11, finished topping off casing with another 2 yards of redi mix slurry, to surface, Pat Stabb on location, job, complete

Plugging Contractor License #: 99977 Name: Quality Oil Well Cementing
Address 1: P.O. Box 32 Address 2: _____
City: Russell State: Kansas Zip: 67665 + 0032
Phone: (785) 483-2025

Name of Party Responsible for Plugging Fees: Unrein Oil Co.
State of Kansas County, Ellis, ss.
Glenn Unrein Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

RECEIVED