

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4448  
Name: Perkins Oil Enterprises Inc.  
Address 1: Box 707  
Address 2: \_\_\_\_\_  
City: Howard State: KS Zip: 67349 + \_\_\_\_\_  
Contact Person: James R. Perkins  
Phone: (620) 3742133  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
1616 Depth to Top: D & A Bottom: \_\_\_\_\_ T.D. 1616  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 0491926200 00  
Spot Description: se-se-se  
SE-SE-se Sec. 25 Twp. 30 S. R. 10  East  West  
330 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Elk  
Lease Name: Stephens Well #: 1  
Date Well Completed: no record  
The plugging proposal was approved on: 1-3-2011 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Plugging Commenced: 1-5-2011  
Plugging Completed: 1-5-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Base K.C.</u>	<u>D &amp; A</u>	<u>9 1/2 #</u>	<u>4 1/2"</u>	<u>1616</u>	<u>none</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 1600. John Elmore pumped 50' cement plug. Pulled tubing to 1225 and John Elmore pumped 50' plug. Pulled to 350 perfs and cemented to top.

Plugging Contractor License #: 34203 Name: Pirate Well Service LLC  
Address 1: PO Box 7 Address 2: \_\_\_\_\_  
City: Howard State: Ks. Zip: 67349 + \_\_\_\_\_  
Phone: (620) 3742301  
Name of Party Responsible for Plugging Fees: James R. Perkins Perkins Oil Enterprises, Inc.

State of Kansas County, Elk, ss.  
James R. Perkins  Employee of Operator or  Operator on above-described well,  
(Print Name)

affirms  
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: James R. Perkins

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
FEB 17 2011  
KCC WICHITA  
DR

# Invoice



Pirate Well Service, LLC.

PO Box 7  
747 E. Jefferson St.  
Howard, KS 67349

Date 1/5/2011  
Invoice # 726

Cell 620-330-3666  
Home 620-374-2301  
Fax 620-374-2301  
kwardlow@sktc.net

### Bill To

Perkins Oil  
Jim Perkins  
P.O. Box 707  
Howard, KS 67349

Terms Net 15

Due Date 1/20/2011

Description	Hours	Rate	Amount
Stephen 1 (plug well) 12/15/10 swab well to see if any oil in hole. 1/5/11 Run tubing in to 1600.42' & pump 50' plug, pull 12 jt to 1225.32' pump 50' plug. Pull 28 jts 343.29' & start to pump top plug. could not get circulation, had to get more gel & water. Run 15 jts back in & pump gel, let it set 30 mins & pull 15 jts & start to pump cement, got circulation & got top plug pumped. Pull last 11 jts & top off, rig down.	9	120.00	1,080.00T
tong usage	2	25.00	50.00T
Pipe Dope		8.00	8.00T

Subtotal \$1,138.00  
 Sales Tax (7.3%) \$83.07  
 Total \$1,221.07  
 Balance Due \$1,221.07

Make check payable to  
Kevin Wardlow

Thank you for  
your business

RECEIVED  
 FEB 17 2011  
 KCC WICHITA

**CORNISH WIRELINE SERVICES, INC.**

P.O. DRAWER H • CHANUTE, KS 66720

620-431-9308

**INVOICE**

**SOLD TO:** PERKINS OIL ENTERPRISES, INC.  
c/o JIM PERKINS  
RR #2, BOX 707  
HOWARD, KANSAS 67349

Date of Invoice 1-7-11

Invoice # 15634

PLEASE RETURN ONE COPY OF  
INVOICE WITH PAYMENT.

DATE OF SERVICE	TYPE OF SERVICE	AMOUNT
12-30-10	<p>STEVENS #1</p> <p>ELK COUNTY, KANSAS</p> <p>PERFORATED TO PLUG WITH 2-1/8" ALUMINUM SHOTS 2 SHOTS AT 350'</p> <p><i>3-Copy Please</i></p> <p>RECEIVED JAN 08 2011</p> <p>BY:.....</p> <p>THANK YOU. WE APPRECIATE YOUR BUSINESS!!</p> <p>TERMS: All invoices are due in full 30 days after invoice date. A FINANCE CHARGE of 1 3/4% (21% per annum) will be assessed after 30 days.</p>	<p>\$200.00</p>

RECEIVED  
FEB 17 2011  
KCC WICHITA

8984

STATEMENT

**ELMORE'S INC.**  
 Box 87 - 776 HWY99  
 Sedan, KS 67361  
 Cell: (620) 249-2519  
 Eve: (620) 725-5538

Date 1-5-11

Customer Perkins Oil  
 Address \_\_\_\_\_  
 City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

Qty.	Description	Price	Amount
55	SKS Cement	9.50	522.50
10	SKS Gel	16.00	160.00
1	SK Hulls	5.00	5.00
4	hr Water Truck	85.00	340.00
4	hr Cement Pump	110.00	440.00
1	Bank Tank	85.00	85.00
			1552.50
	Plug Job Stevenson #1	Tax	128.86
			1681.36
	Gel Hole At 1100'		
	Spotted 5 SKS Cement Pulled		
	Up to 1200' Spotted 5 SKS		
	Pulled up to 350' Middle Plug		
	Fell Ran Back To 1000' Gel		
	Hole with 5 more SK & Hulls		
	Spotted 10 SKS Cement Pulled Up		
	To 350 Cemented To Surface With		

Thank You -- We appreciate your business! 35 SKS.

Rec'd. by \_\_\_\_\_

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

RECEIVED  
 FEB 17 2011  
 KCC WICHITA

# Invoice



Pirate Well Service, LLC.

PO Box 7  
747 E. Jefferson St.  
Howard, KS 67349

Date 1/5/2011  
Invoice # 726

Cell 620-330-3666  
Home 620-374-2301  
Fax 620-374-2301  
kwardlow@sktc.net

### Bill To

Perkins Oil  
Jim Perkins  
P.O. Box 707  
Howard, KS 67349

Terms Net 15

Due Date 1/20/2011

Description	Hours	Rate	Amount
Stephen 1 (plug well) 12/15/10 swab well to see if any oil in hole. 1/5/11 Run tubing in to 1600.42' & pump 50' plug, pull 12 jt to 1225.32' pump 50' plug. Pull 28 jts 343.29' & start to pump top plug. could not get circulation, had to get more gel & water. Run 15 jts back in & pump gel, let it set 30 mins & pull 15 jts & start to pump cement, got circulation & got top plug pumped. Pull last 11 jts & top off, rig down.	9	120.00	1,080.00T
tong usage	2	25.00	50.00T
Pipe Dope		8.00	8.00T

Subtotal \$1,138.00  
 Sales Tax (7.3%) \$83.07  
 Total \$1,221.07

Make check payable to  
Kevin Wardlow

Balance Due \$1,221.07

Thank you for  
your business

RECEIVED  
 FEB 17 2011  
 KCC WICHITA