

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5141  
Name: Zenith Drilling Corporation  
Address 1: PO Box 780428  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67278 + 0.4 2.8  
Contact Person: Charles Schmidt  
Phone: (316) 755-3523  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing Depth to Top: 2939' Bottom: 3150 T.D. 3275  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 167-05296-0000  
Spot Description: CONTRACT. 10/18/50 PER OPER.  
SE. NE. NE Sec. 35 Twp. 15 S. R. 13  East  West  
990 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Russell  
Lease Name: Sellens Well #: 5  
Date Well Completed: Unknown  
The plugging proposal was approved on: 11/16/10 (Date)  
by: Dave Dolechek (KCC District Agent's Name)  
Plugging Commenced: 11/22/2010  
Plugging Completed: 11/22/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Lansing	Oil/ Water	Surface	8 5/8"	520'	0
		Production	5 1/2"	3338	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/ tbg to 3075'.  
Mix & pump 10 sks gel, 50 sx 60/40 w. 4% gel, 1/4# floseal, w/ 200# hulls 3075' - 2625'.  
Pull tbg to 1600'. Mix and pump 100 sx 60/ 40 from 1600' - 700'.  
POH w/ tbg. Mix 5 sx 60/ 40, press. to 300#.  
Connect to 8 5/8", press. to 300#

Plugging Contractor License #: KLN 4072 Name: H2 Plains LLC  
Address 1: PO Box 346 Address 2: \_\_\_\_\_  
City: Ness City State: Kansas Zip: 67560 +  
Phone: (785) 798-3995  
Name of Party Responsible for Plugging Fees: Zenith Drilling Corporation  
State of Kansas County, Sedgwick, ss.  
RUSSELL D. BRIGGS  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: [Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
SEP 17 2011  
2-17-11  
KCC WICHITA

Dec. 6. 2010 1:41PM Allied Cementing Co LLC Va. 2525 2. 2  
**ALLIED CEMENTING CO., LLC.** 30144

REMIT TO P.O. BOX 31  
 RUSSELL, KANSAS 67665

SERVICE POINT  
Russell

DATE <u>11/22/10</u>	SEC <u>35</u>	TWP <u>15</u>	RANGE <u>12</u>	CALLED OUT	ON LOCATION	JOB START <u>10:45 AM</u>	JOB FINISH <u>11:45 AM</u>
LEASE <u>Sellers</u>	WELL # <u>5</u>	LOCATION <u>Seward to a Comptrol</u>			COUNTY <u>Russell</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)		<u>1 N 2E 1/4 S. W. 15</u>					

CONTRACTOR <u>Plain well service</u>	OWNER
TYPE OF JOB <u>PTA</u>	CEMENT <u>Use 10 Gal 200 skt 500 4h-lls</u>
HOLE SIZE	AMOUNT ORDERED <u>760 gal 42 Gal</u>
CASING SIZE <u>5 1/2</u>	<u>14" H. Seal</u>
TUBING SIZE <u>2 3/8</u>	<u>11 Gal 200 4h-lls</u>
DRILL PIPE	COMMON <u>120</u> @ <u>15.50</u> <u>1890.00</u>
TOOL	POZMIX <u>80</u> @ <u>2.00</u> <u>160.00</u>
PRES. MAX	GEL <u>18</u> @ <u>20.25</u> <u>364.50</u>
MEAS. LINE	CHLORIDE
CEMENT LEFT IN CSG.	ASC
PERFS.	<u>Et. Seal 50</u> @ <u>2.50</u> <u>125.00</u>
DISPLACEMENT	<u>Hull</u> @ <u>3.10</u> <u>248.00</u>

EQUIPMENT	
PUMP TRUCK	CEMENTER <u>Shane</u>
# <u>412</u>	HELPER <u>Heath</u>
BULK TRUCK	
# <u>461</u>	DRIVER <u>Gary</u>
BULK TRUCK	
#	DRIVER

HANDLING <u>2.25</u>	@ <u>2.25</u>	<u>450.00</u>
MILEAGE <u>10.66</u>	@ <u>20.00</u>	<u>213.20</u>
		TOTAL <u>3716.25</u>

REMARKS:  
Tuber 3275' Mixed 10 Gal  
5 skt 200 4h-lls Pullout  
up to 1600' Mixed 100 skt  
with 300 4h-lls Pullout up to  
500' Mixed 45 skt to Circulate  
Comp. l. Come out at Hole  
but was on mixed 5 skt that  
to G. Joe printed on Backside  
pressed up to 300 ft

CHARGE TO: Zenith  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

*Thanks!*

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME \_\_\_\_\_  
 SIGNATURE Chad Walker

SERVICE		
DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>675.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>20</u>	@ <u>7.00</u>	<u>140.00</u>
MANIFOLD	@	
		TOTAL <u>1,055.00</u>

PLUG & FLOAT EQUIPMENT		
	@	
	@	
	@	
	@	
	@	
		TOTAL _____

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES 2,110.25  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

RECEIVED  
 FEB 17 2011

KCC WICHITA



PO BOX 31 Russell, KS 67685

*12/6/10 Sharon  
for 316-684-8805*

# INVOICE

Invoice Number: 125407

Invoice Date: Nov 22, 2010

Page: 1

Voice: (785) 483-3887

Fax: (785) 483-5568

<b>Bill To:</b>
Zenith Drilling Corp. P. O. Box 780428 Wichita, KS 67278-0428

Customer ID	Well Name# or Customer P.O.	Payment Terms	
Zeni	Selens #5	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS2-03	Russell	Nov 22, 2010	12/22/10

Quantity	Item	Description	Unit Price	Amount
120.00	MAT	Class A Common	13.50	1,620.00
80.00	MAT	Pozmix	7.55	604.00
18.00	MAT	Gel	20.25	364.50
50.00	MAT	Flo Seal	2.45	122.50
5.00	MAT	Cottonseed Hulls	31.05	155.25
200.00	SER	Handling	2.25	450.00
20.00	SER	Mileage 200 sx @ .10 per sk per mi	20.00	400.00
1.00	SER	Plug to Abandon	875.00	875.00
20.00	SER	Pump Truck Mileage	7.00	140.00

ALL PRICES ARE NET, PAYABLE 30 DAYS FOLLOWING DATE OF INVOICE. 1 1/2% CHARGED THEREAFTER, IF ACCOUNT IS CURRENT, TAKE DISCOUNT OF 2.0 \$ <u>946.95</u>	Subtotal	4,731.25
	Sales Tax	392.69
	Total Invoice Amount	5,123.94
	Payment/Credt Applied	
	<b>TOTAL</b>	<b>5,123.94</b>

ONLY IF PAID ON OR BEFORE  
 Dec 17, 2010

RECEIVED  
 FEB 17 2011  
 KCC WICHITA