

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33358
Name: Renick Energy LC
Address 1: 10502 6 Road
Address 2: _____
City: Ingalls State: KS Zip: 67853
Contact Person: Mark Renick
Phone: (620) 260 7301
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filled? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 055-203010000
Spot Description: SE NE NE SW Sec. 34 Twp. 25 S. R. 31 East West
2166 feet from North / South Line of Section
2730 feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Finney
Lease Name: Minter-Wilson Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 5-12-10 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 12-7-10
Plugging Completed: 12-8-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8	577	-
			5 1/2	2669	1000

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1 1/2 to 1370. Mixed 100 lb hulls & 25 sx cmt to plug @ top of junk from 1370 to 1170. Tag plug @ 1300. Recover 5 1/2.
Ran 1 1/2 to 1000. Circ hole w/mud & mixed 75 sx plug 1000 to 775 40 sx 570 to 450 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent And Horton Plugging Inc.
Address 1: Rt 1 Box 49BA Address 2: _____
City: Tyrone O State: OK Zip: 73951-9731
Phone: (580) 854 6515

Name of Party Responsible for Plugging Fees: Renick Energy LC
State of KANSAS County: GRAY, ss.
Michael R Renick, Registered Agent Employee of Operator or Operator (if above is plugging) WICHITA
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Michael R Renick, Registered Agent Renick Energy LC

DR