

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 30458 Name: RJM Oil Company, Inc. Address 1: PO Box 256 Address 2: City: Claflin State: KS Zip: 67525 Contact Person: Chris Hoffman Phone: (620) 786-8744 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D.

API No. 15 - 009-25541-00-00 Spot Description: NE NE NE Sec. 12 Twp. 19 S. R. 12 East West 330 Feet from North South Line of Section 330 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barton Lease Name: Kowalsky Family Well #: 2 Date Well Completed: 4/14/2011 The plugging proposal was approved on: 4/14/2011 (Date) by: Bruce Basye (KCC District Agent's Name) Plugging Commenced: 4/14/2011 Plugging Completed: 4/14/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8", 310', 0'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 185 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal per sack, 1st plug @ 3390' with 25 sacks, 2nd plug @ 650' with 25 sacks, 3rd plug @ 360' with 80 sacks, 4th plug @ 40' to surface with 10 sacks, 15 sacks for mouse hole, 30 sacks for rat hole. Plug was down @ 3:00 pm on 4/14/2011. Cement did circulate, and cemented by Quality (Ticket #5065).

RECEIVED APR 19 2011

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc. Address 1: PO Box 276 Address 2: City: Ellinwood State: Kansas Zip: 67526 Phone: (620) 564-3800 Name of Party Responsible for Plugging Fees: RJM Oil Company, Inc. State of Kansas County: Barton Jennifer Heape (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jennifer Heape

SOUTHWIND DRILLING, INC.
PLUGGING ORDERS AND REPORTS

Lease: Kowalsky Family #2

Plugging received from KCC representative:

Name: Bruce Basye Date 4-14-11 Time 8:08 A.M.

1st plug @ 3390 ft. 25 sx. Stands: 54

2nd plug @ 650 ft. 25 sx. Stands: 10½

3rd plug @ 360 ft. 80 sx. Stands: 5½

4th plug @ 40 ft. 10 sx. Stands: 1

5th plug @ — ft. — sx. Stands: —

Mousehole 15 sx.

Rahole 30 sx.

Total Cement used: 185 sx.

Type of cement 60/40 poz 4% gel ¼" Flo Seal per sx

Plug down @ 3:00 p.m. 4-14-11 cem. did circ.

Call KCC When Completed:

Name: Ray Dinkel Date 4-15-11 Time 8:08 A.M.

RECEIVED

APR 19 2011

KCC WICHITA