

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6804
Name: LACHENMAYR OIL, LLC
Address 1: P. O. BOX 526
Address 2: _____
City: NEWTON State: KS Zip: 67114 + _____
Contact Person: Howard Lachenmayr
Phone: (316) 558-3625
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-151-22363-00-00
Spot Description: C NW NW NE 29-26S-14W
C NW NW NE Sec. 29 Twp. 26 S. R. 14 East West
330 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: PRATT
Lease Name: Achterberg Trust Well #: 1
Date Well Completed: 1/24/2011
The plugging proposal was approved on: 1/21/2011 (Date)
by: ERIC MACLAREN (KCC District Agent's Name)
Plugging Commenced: 1/24/2011
Plugging Completed: 1/24/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
CONDUCTOR		NEW	10.75	363	0' RECEIVED
SURFACE		NEW	8.625	983'	0' APR 22 2011
					KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran pipe to 1010', pumped to break circulation, mixed 50 sks. 60/40 pozmix 4%gel, 3 1/2%cc, 1/2 poly flake per sack, displaced with 10 bbls. of water, pulled pipe to 390', mixed 100 sks 60/40 pozmix, 4% gel, displaced with 4 1/2 bbls. of water, pulled pipe to 60', mixed 40 sks 60/40 pozmix, 4% gel, circulated cement to surface, pulled pipe out, ran one joint into rat hole, mixed 30 sks 60/40 pozmix 4% gel and ran one joint into mouse hole, mixed 20 sks 60/40 pozmix, 4% gel topped holes off with 15 sks 60/40 pozmix 4% gel. Job complete at 7:30 AM.

Plugging Contractor License #: 5123 Name: PICKRELL DRILLING COMPANY, INC.
Address 1: 100 S. MAIN, SUITE 505 Address 2: _____
City: WICHITA State: KS Zip: 67202 + 3738
Phone: (316) 262-8427
Name of Party Responsible for Plugging Fees: LACHENMAYR OIL, LLC
State of KANSAS County, HARVEY, ss.
HOWARD LACHENMAYR Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Howard Lachenmayr

DR