

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6039
Name: L.D. Drilling, Inc.
Address 1: 7 SW 26th Avenue
Address 2: _____
City: Great Bend State: KS Zip: 67530 + _____
Contact Person: Mike Kasselmann
Phone: (620) 793-3051
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-24776-00-00
Spot Description: S/2 SE SE
_____ Sec. 16 Twp. 18 S. R. 15 East West
330 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Kuhlman Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Bruce Rodie (KCC District Agent's Name)
Plugging Commenced: 1-10-11
Plugging Completed: 1-13-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	820'	None
			4-1/2"	3575'	1823'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3150' and 4 sacks cement. Cut casing loose @1823', pulled up to 1791', pumped 100 sacks cement and 200# hulls, pulled up to 850', pumped 40 sacks cement and 100# hulls, pulled up to 500' and pumped 190 sacks cement to surface, topped off with 30 sacks cement. 60/40 pos, 4% gel. Plugging Complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: _____
City: Chase State: Kansas Zip: 67524 + 0467
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc.
State of Kansas County, Rice, ss.
Mike Kelso (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

FEB 09 2011

KCC WICHITA