

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33406
Name: Garner, Thomas
Address 1: 305 E. 7th
Address 2: _____
City: St. John State: KS Zip: 67576 + 1652
Contact Person: Tom Garner
Phone: (620) 549-6618
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-00735-00-00
Spot Description: _____
SE SW SE Sec. 8 Twp. 18 S. R. 13 East West
330 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Karst Well #: 1
Date Well Completed: 1954
The plugging proposal was approved on: _____ (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 10/18/10
Plugging Completed: 10/19/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	744'	450 Sacks Cement
		Production	5.5	3294'	125 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Casing head had cement in it. Log-Tech shot holes at 1500', 750', 450' & 200'. Ran 2600' of tubing & pumped 10 gel & 50 sacks cement. Pulled to 1500' & pumped 50 sacks cement. Pulled to 750' & pumped 100 sacks cement to surface. Pulled rest of tubing. Hooked up to 5 1/2" casing & pumped 20 sacks cement. Shut in 250 psi.

RECEIVED

MAR 18 2011

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US Hwy 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410

KCC WICHITA

Name of Party Responsible for Plugging Fees: Garner, Thomas
State of Kansas County, Barton, ss.
Thomas Garner
(Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct; so help me God.

Signature: [Signature]