TO: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PŁUGGING

130 SOUTH MARKET, SUITE 2078 **WICHITA, KANSAS 67202**

API Well Number: 15-163-03612-00-00

Spot: NESESE

Sec/Twnshp/Rge: 17-9S-16W

940 feet from S Section Line,

405 feet from E Section Line

Lease Name: DORR B

Well #: 1

County: ROOKS

Total Vertical Depth: 3398 feet

Operator License No.: 6569

Op Name: SCHMITT, CARMEN, INC.

Address: PO BOX 47

GREAT BEND, KS 67530

Depth (ft) Pulled (ft) Comments String Size

SURF 8.625 244 0

w/unknown sxs cmt

PROD 4.5 3242 0

w/unknown sxs cmt

Well Type: OlL

UIC Docket No:

Perfs:

Top

3300

3294

3212

3210

3156

3089

Bot

3304

3298

3216

3221

3162

3095

Date/Time to Plug: 04/05/2011 8:30 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Revd. from: CURTIS HITSCHMAN

Company: SCHMITT, CARMEN, INC.

Phone: (620) 793-5100

Thru Comments

Proposed 04/05/2011 - Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging 04/06/2011 - Ordered 400 sxs 60/40 pozmix - 4% gel - 100 sxs with 4% c.c.

Method: Casing scraper stuck at 2200'.

Squeezed at 870' - 1250' with 240 sxs.

Perforated at 775'.

Plugging Proposal Received By: CASE MORRIS

Date/Time Plugging Completed: 04/11/2011 10:15 AM

WitnessType: PARTIAL

KCC Agent: PAT BEDORE

Actual Plugging Report:

04/05/2011 - Ran tubing to 1650' - pumped 155 sxs cement with 300# hulls.

Pulled tubing to 1000' - pumped 25 sxs cement.

Pulled tubing to 763'. L-K Wireline perforated casing at 775' - pumped 75 sxs cement with 100# hulls. Well went on vacuum - shut down for one hour.

Pumped another 50 sxs cement with 100# hulls - well still went on vacuum. Shut down - pulled tubing - will go back in the hole in the morning and tag cement.

04/06/2011 - Ran tubing back in the hole to 1592'. Did not tag any cement. - pumped 100 sxs cement - 4% c.c. with 300# hulls. Pulled tubing and let set for two hours.

Ran tubing back in hole to 1000' - pumped 75 sxs cement with 250# hulls. Well went on vacuum. Let set for 15 minutes - pumped 50 sxs cement - 4% cc.

Pulled all tubing and let set overnight.

The following was not witnessed - approved by Case Morris, District Supervisor:

04/07/2011 - Pumped 480 bbls drilling mud with 600# hulls.

04/08/2011 - Drilled bridge at 180'. Got tubing to 620' and stacked out - well still on vacuum.

04/11/2011 - Tubing at 620' - pumped 25 sxs cement with 200# hulls.

Pulled tubing - let set for 1 1/2 hours - tagged cement at 280' - pumped 40 sxs cement to circulate to surface.

Pulled tubing. Topped off 4 1/2" casing with 5 sxs cement.

Hooked to 8 5/8" x 4 1/2" annulus and pumped 20 sxs cement.

S.I.P. 200#.

KCC WICHITA

OUALITY OIL WELL CEMENTING COMPANY-TICKET #5055. Remarks:

Plugged through: TBG

District: 04

Pat Bedon Signed

(TECHNICIAN)

CM