

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21667-00-00
Spot: NENE Sec/Twnshp/Rge: 22-29S-32W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: STOOPS WEBBER Well #: 5
County: HASKELL Total Vertical Depth: 5643 feet

Operator License No.: 33036
Op Name: STRATA EXPLORATION, INC.
Address: PO BOX 401
FAIRFIELD, IL 62837

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4850		WITH 2 SX CMT
SURF	8.625	1805		WITH 750 SX CMT
PROD	4.5	5210	2030	WITH 205 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/30/2011 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: SHANE PELTON Company: STRATA EXPLORATION Phone: (719) 340-8987

Proposed Plugging Method: CIBP @ 4850' WITH 2 SX CMT. PLUG AT 1830' WITH 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2011 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4850' WITH 2 SX CMT. SHOT CASING AT 3000'. COULD NOT PULL. SHOT CASING AT 2030' & PULLED CASING. 1ST PLUG AT 1835' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4921	4931		FT. SCOTT

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

APR -7 2011

KCC DODGE CITY

RECEIVED
APR 18 2011
KCC WICHITA

Form CP-2/3

4/25