

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20415-00-00
Spot: NENENW Sec/Twnshp/Rge: 20-11S-18W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: FRISBIE M Well #: 1M
County: ELLIS Total Vertical Depth: 3599 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	322	0	w/170 sxs cmt
PROD	5.5	3599	0	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2011 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Tubing parted at 1860'.
Perfed at 310' - 650' - 1250' - 1750'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2011 6:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 1800' - pumped 115 sxs 60/40 pozmix - 4% gel.
POOH. Perforated.
Ran tubing to 1850' - pumped 80 sxs cement with 100# hulls.
Pulled to 1250' - circulated with 75 sxs cement with 200# hulls.
POOH. Pumped 10 sxs cement down backside.
S.I.P. 200#.
Tied onto 4 1/2" and pumped 15 sxs cement.
S.I.P. 100#.

Perfs:

Remarks: QUALITY WELL SERVICE, INC.

Plugged through: TBG

RECEIVED
APR 22 2011
KCC WICHITA

District: 04

Signed Case Morris
(TECHNICIAN)

Form CP-2/3

✓ 4/25

APR 15 2011