

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00853-00-00
Spot: SWSENW Sec/Twnshp/Rge: 2-15S-18W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BRULL Well #: 1
County: ELLIS Total Vertical Depth: 3603 feet

Operator License No.: 3194
Op Name: TRI UNITED, INC
Address: 950 270TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208	0	w/140 sxs cmt
PROD	5.5	3601	0	w/175 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2011 1:00 PM
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Superior Well Service perfed at 1650' - 1200' - 550' - 200'.
Junk in the hole at 2200'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2011 4:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Tri United RIH with tubing to 2150'.
Allied rigged to tubing and mixed and pumped 50 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1650' - Allied rigged to tubing and mixed and pumped 165 sxs cement with 500# hulls mixed in - no circulation.
Pulled tubing to 825' - pumped 120 sxs cement with 500# hulls to circulate cement up 5 1/2" casing.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 30 sxs cement to circulate up 8 5/8" casing.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3587	3603		Arbuckle
3294	3518		LKC

RECEIVED
APR 18 2011
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS P B LEIKER A #1. ALLIED CEMENTING COMPANY-TICKET #36915.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

4/25

APR 14 2011