

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26122-00-00
Spot: S2NENW Sec/Twnshp/Rge: 20-14S-18W
950 feet from N Section Line, 1950 feet from W Section Line
Lease Name: PFANNENSTIEL Well #: 3
County: ELLIS Total Vertical Depth: 3744 feet

Operator License No.: 32504
Op Name: WERTH, AARON J. DBA BLACKHAWK
Address: 1607 OAKMONT
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1294		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/03/2011 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: BLACKHAWK PRODUCTION COM Phone: (785) 625-2041

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE
Date/Time Plugging Completed: 04/03/2011 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

1st. Plug at 3650' w/25 sxs.
2nd. Plug at 1294' w/25 sxs.
3rd. Plug at 600' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED
APR 18 2011
KCC WICHITA

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

Form CP-2/3
4/25

APR 07 2011