

4/05 - Jo Nick for r.

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-003- 01846-00-00

Spot: <sup>SW</sup> SE SW NW Sec 13 Twp 21 S Rng 20 ☒ E / ☐ W  
 3012 Feet from ☐ N / ☒ S Line of Section  
 4646 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 38.220450 Long: 95.164216 Date: 2/4/10

Lease Name: West Van Winkle Well #: S-25X (WVW29)

County: Anderson Total Vertical Depth: 618 feet

Operator License No: 34170	String	Size	Depth	Pulled	Comments
Op Name: Sirius Energy Corp.					
Address 1: 526 Country Pl. South					
Address 2:					
City: Abilene					
State: TX Zip Code: 79606 -					

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: Date/Time to Plug: 1/27/10 / 12:00 pm

Plug Co License No.: 99998 Plug Co. Name: Company Tools

Proposal Recvd from: Randy Teeter Company Name: Sirius Energy Phone: (785) 448-8571

Proposed  
Plugging  
Report:

FILL WELL WITH CEMENT FROM BOTTOM TO SURFACE ON INSIDE AND STAGE PLUGS ON BACKSIDE TO SURFACE.

Plugging Proposal Received By: Levi Short Witness Type: COMP - Complete 100%

Date/Time Plugging Completed: 1/27/10 / 3:00 pm KCC Agent: Levi Short

Actual Plugging Report: Perfs: Top Bottom Thru

RUN 3/4 INCH INSIDE 2 INCH CASING TO 618 FEET AND FILL WITH 8 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO 395 FEET AND PUMP 20 SACKS OF CEMENT THEN TO 250 FEET AND PUMP 92 SACKS OF CEMENT TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 120 SACKS OF CEMENT.

RECEIVED  
APR 05 2010  
KCC WICHITA

Remarks:

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03 Levi Short (PIRT) (Technician)

Form: District Plugging Report -