

465 - 20 Nick for n.

API Well Number: 15-003- 01851- 00-00

Spot: ^{NW} NE SW SW NW Sec 13 Twp 21 S Rng 20 E / W
3010 Feet from N / S Line of Section
4975 Feet from E / W Line of Section

GPS: Lat: 38.220440 Long: 95.165364 Date: 3/24/10

Lease Name: West Van Winkle Well #: S-27X (WVW37)

County: Anderson Total Vertical Depth: 609 feet

Kansas Corporation Commission

District Plugging Report

Operator License No: 34170	String	Size	Depth	Pulled	Comments
Op Name: Sirius Energy Corp.					
Address 1: 526 Country Pl. South					
Address 2:					
City: Abilene					
State: TX Zip Code: 79606					

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: Date/Time to Plug: 2/3/10 / 12:00 pm

Plug Co License No.: 99998 Plug Co. Name: Company Tools

Proposal Rcvd from: Randy Teeter Company Name: Sirius Energy Phone: (785) 448-8571

Proposed
Plugging
Report:

FILL WELL WITH CEMENT FROM BOTTOM TO SURFACE ON INSIDE AND STAGE PLUGS ON BACKSIDE TO SURFACE.

Plugging Proposal Received By: Levi Short Witness Type: ZERO - None

Date/Time Plugging Completed: 2/3/10 / 3:00 pm KCC Agent: Levi Short

Actual Plugging Report: Perfs: Top Bottom Thru

RUN 3/4 INCH INSIDE 2 INCH CASING TO 609 FEET AND FILL WITH 8 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO 435 FEET AND PUMP 24 SACKS OF CEMENT THEN TO 250 FEET AND PUMP 88 SACKS OF CEMENT TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 120 SACKS OF CEMENT.

RECEIVED
APR 05 2010
KCC WICHITA

Remarks

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 Levi Short (PIRT) *L. Short*
(Technician)

Form: District Plugging Report -