

4/05 - Jo Nick for r.

API Well Number: 15-003- 01840-00-00

Kansas Corporation Commission

Spot: NW SW NW Sec 13 Twp 21 S Rng 20 E / W

District Plugging Report

3335 Feet from N / S Line of Section

4985 Feet from E / W Line of Section

GPS: Lat: 38.221333 Long: 95.165383 Date: 2/4/10

Lease Name: West Van Winkle Well #: U-27X (WVW16)

County: Anderson Total Vertical Depth: 630 feet

Operator License No: 34170	String	Size	Depth	Pulled	Comments
Op Name: Sirius Energy Corp.					
Address 1: 526 Country Pl. South					
Address 2:					
City: Abilene					
State: TX Zip Code: 79606					

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: Date/Time to Plug: 1/27/10 / 12:00 pm

Plug Co License No.: 99998 Plug Co. Name: Company Tools

Proposal Rcvd from: Randy Teeter Company Name: Sirius Energy Phone: (785) 448-8571

Proposed Plugging Report:

FILL WELL WITH CEMENT FROM BOTTOM TO SURFACE ON INSIDE AND STAGE PLUGS ON BACKSIDE TO SURFACE.

Plugging Proposal Received By: Levi Short Witness Type: COMP - Complete 100%

Date/Time Plugging Completed: 1/27/10 / 3:00 pm KCC Agent: Levi Short

Actual Plugging Report: Perfs: Top Bottom Thru

RUN 3/4 INCH INSIDE 2 INCH CASING TO 630 FEET AND FILL WITH 8 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO 418 FEET AND PUMP 20 SACKS OF CEMENT THEN TO 250 FEET AND PUMP 94 SACKS OF CEMENT TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 122 SACKS OF CEMENT.

RECEIVED APR 05 2010 KCC WICHITA

Remarks

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 Levi Short (PIRT) (Technician)

Form: District Plugging Report