

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19556-00-00
Spot: NWSESW Sec/Twnshp/Rge: 24-23S-3E
966 feet from S Section Line, 3668 feet from E Section Line
Lease Name: BUSENITZ Well #: 1
County: BUTLER Total Vertical Depth: 2505 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>SURF</u>	<u>8.625</u>	<u>120</u>		
<u>PROD</u>	<u>4.5</u>	<u>2471</u>		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2010 10:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK
Date/Time Plugging Completed: 11/24/2010 11:30 AM

Witness Type: COMPLETE (100%)
KCC Agent: SHANE JONES

Actual Plugging Report:

CYCLONE PULLED RODS AND TUBING AND DROPPED SAND. THEY TAGGED SAND @2412' AND CAPPED IT W/S SX. DYNA LOG PERFORATED @ 250'. CYCLONE RAN IN 250' OF TUBING AND LOADED THE HOLE WITH WATER. COPELAND ARRIVED AND TIED ON TO TUBING. THEY STARTED PUMPING CEMENT. THEY HAD WATER CIRCULATING UP THE BACKSIDE. THEY GOT CEMENT CIRCULATED TO THE SURFACE OF THE CASING. WE ARE STILL JUST GETTING WATER UP THE BACKSIDE. AT 165 SXS IT WAS DECIDED TO PULL TUBING AND TIE ON TO THE CASING. COPELAND PUMPING DOWN THE 4.5" AND WAS ABLE TO GET CEMENT TO CIRCULATE TO THE SURFACE ON THE BACKSIDE. TK #35173, 210 SXS 60/40 POS W/4% GEL. 11/29/2010 TOP PLUG 5' INSIDE CASING AND DOWN 45' IN THE 8 5/8". OPERATOR WILL CONTACT ME WHEN GETS TOPPED OFF AND CAN RECHECK.

Perfs:


Top	Bot	Thru	Comments
2471	2505	OH	

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED

DEC 10 2010

Form CP-2/3

KCC WICHITA

154