

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-01594-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 24-23S-3E  
4945 feet from S Section Line, 1042 feet from E Section Line  
Lease Name: HINZ Well #: 4  
County: BUTLER Total Vertical Depth: 2468 feet

Operator License No.: 5920  
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G  
Address: PO BOX 522  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2390		
SURF	8.633	142		75 SX
PROD	5.5	2440		75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2010 11:30 AM  
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY P. BANDY Company: \_\_\_\_\_ Phone: (620) 245-8071

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/24/2010 1:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

CYCLONE PULLED RODS AND TUBING AND DROPPED SAND. DYNALOG OUT AND SET CIBP @2390 & CAPPED W/2SX . DYNALOG THEN PERFORATED @ 250'. CYCLONE RAN IN 250' OF TUBING. COPELAND TIED ON AND LOADED THE HOLE WITH 12.5 BBL WATER CIRCULATED UP THE BACKSIDE. COPELAND SWITCHED TO CEMENT AND GOT CEMENT CIRCULATED TO THE SURFACE OF THE 5.5". CYCLONE THEN PULLED TUBING AND COPELAND TIED ON TO THE 5.5" AND PUMPED CEMENT. COPELAND GOT CEMENT TO CIRCULATE UP THE BACKSIDE. SHUT IN THE 5.5" WITH SWEDGE AND VALVE. TK #35174 140 SX 60/40 POS W/4% GEL. 11/29/2010 TOP PLUG @ SURFACE OF 5 1/2" AND DOWN 18' INSIDE OF 8 5/8". OPERATOR WILL CONTACT WHEN IS TOPPED OFF SO CAN BE RECHECKED.


Perfs:

Top	Bot	Thru	Comments
2440	2468	OH	MISSISSIPPI

Remarks:

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN) RECEIVED

DEC 10 2010

Form CP-2/3

KCC WICHITA

✓