

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-19043-00-00
Spot: NENWSW Sec/Twnshp/Rge: 4-32S-1W
2128 feet from S Section Line, 3991 feet from E Section Line
Lease Name: WELLINGTON UNIT Well #: 118
County: SUMNER Total Vertical Depth: 3696 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5	450		
CIBP	5.5	3600		
PROD	5.5	3648		50 SX
STRL	10	346		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/05/2009 8:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: JASON BRUNS Company: BEREXCO LLC Phone: (620) 226-2080

Proposed Plugging Method: SET CIBP 3600' AND 2 SKS CMT. SET CIBP 450' AND 2 SKS CMT. PERF AT 400' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2009 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3600' TO COVER THE OPEN HOLE. ANOTHER CIBP WAS SET AT 450' AND CAPPED WITH 2 SKS OF CMT. THE CASINIG WAS PERFD AT 400' AND CMT WAS CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3648	3696	OH	

Remarks: ALLIED CMTG 60/40 4% GEL 210 SKS

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED

DEC 10 2010

KCC WICHITA CP-2/3

JK