

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05919-00-00
Spot: SENWSW Sec/Twnshp/Rge: 19-19S-10W
1916 feet from S Section Line, 4190 feet from E Section Line
Lease Name: DOLL B Well #: 1
County: RICE Total Vertical Depth: 3318 feet

Operator License No.: 7030
Op Name: JOHN ROY EVANS OIL COMPANY LLC
Address: 405 FOURTH ST BOX 385
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3136		
SURF	8.625	190		175 SX
PROD	5.5	3314	1441	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2010 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING INC. Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/28/2010 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2950' AND CAP WITH 5 SX'S CEMENT. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF. TOPPED OFF WITH 10 SX'S CEMENT ON 11-1-2010.

Perfs:

Top	Bot	Thru	Comments
3100	3108	CSG	

RECEIVED
NOV 04 2010
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND C-37376

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)