

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23306-00-00  
Spot: NESWSESW Sec/Twnshp/Rge: 11-22S-14W  
358 feet from S Section Line, 1705 feet from W Section Line  
Lease Name: BRINING Well #: 1  
County: STAFFORD Total Vertical Depth: 3911 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE.  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	854		WITH 400 SX CMT
PROD	5.5	3910	2561	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2010 10:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: SAND TO 3515' & 5 SX CMT. PLUG AT 880' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/12/2010 11:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3740' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 880' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3806	3810		
3630			
3583	3587		
3565	3570		

Remarks: USED 060/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED  
OCT 22 2010  
KCC WICHITA

District: 01

RECEIVED

OCT 15 2010

KCC DODGE CITY

Signed Richard W. Lacey  
(TECHNICIAN)

Form CP-213