

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-00406-00-00  
Spot: SESESE Sec/Twnshp/Rge: 33-18S-2W  
328 feet from S Section Line, 409 feet from E Section Line  
Lease Name: LARSON A Well #: 1  
County: MCPHERSON Total Vertical Depth: 2980 feet

Operator License No.: 32731  
Op Name: LEWIS OIL & GAS OF GALVA, INC.  
Address: PO BOX 195  
GALVA, KS 67443

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| SURF   | 8    | 206        |             |          |
| PROD   | 5    | 2965       |             |          |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2010 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 755-2653

Proposed Plugging Method: SAND @ 2910', DUMP BAIL 5 SXS ON TOP. CUT CASING, 35 SXS @ 400', CIRCULATE FROM 260'-0' AS PER KCC RULES & REGS

Plugging Proposal Received By: SHANE JONES Witness Type: NONE  
Date/Time Plugging Completed: 11/24/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @2910', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 800'. PULLED CASING @ 400', COPELAND ACID MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL AND DISPLACED IN OPEN HOLE. PULLED CASING @ 260', COPELAND AND ACID MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. COPELAND ACID CEMENT TICKET #37398.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2965 | 2980 | OH   |          |

Remarks: PLUGGED DUE TO 10-YR RULE / COMPLIANCE ISSUE

Plugged through: CSG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

RECEIVED  
DEC 10 2010 CP-2/3  
KCC WICHITA

12