

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20918-00-00
Spot: SENWNESE Sec/Twnshp/Rge: 4-13S-14W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: MACHIN Well #: 4
County: RUSSELL Total Vertical Depth: 3100 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	230	0	w/unknown sxs cmt
PROD	5.5	3100	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2010 11:30 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: JOHN DRISCOLL Company: LOEWEN OPEERATOR, INC. Phone: (785) 483-9580

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 400# hulls.
Iron in the well. Tried for two days to get down well.
Had to start over everyday at 390' and hit iron at 629'.
Circulated all night in order to plug the next day.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2010 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Tubing at 610' - pumped 80 sxs cement with 200# hulls - cement circulated.
POOH. Hooked to casing - pumped 50 sxs cement.
Max. P.S.I. 450#. S.I.P. 350#.
Hooked to Braden head and pumped 5 sxs cement.
Max. P.S.I. 250#. S.I.P. 205#.

Perfs:

RECEIVED
NOV 29 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #33721.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Form CP-2/3

NOV 23 2010