

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20230-00-00
Spot: NESWNE Sec/Twnshp/Rge: 2-10S-15W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: FINNESY Well #: 3
County: OSBORNE Total Vertical Depth: 3538 feet

Operator License No.: 7030
Op Name: JOHN ROY EVANS OIL COMPANY LLC
Address: 405 FOURTH ST BOX 385
CLAFILIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	701	0	250 sxs
T1	2.375	3485		
PROD	4.5	3530	0	200 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2010 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY KIRMER Company: JOHN ROY EVANS OIL COMPANY Phone: (620) 793-2026

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Parted tubing in the hole at 2888'. Plug at 3116'.
Perforated at 1500' - 1140' - 690'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2010 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2868' - pumped 150 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1497' - pumped 80 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 683' - pumped 80 sxs 60/40 pozmix - 4% gel to circulate to surface.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 20 sxs 60/40 pozmix - 4% gel.
Brought cement to surface in 4 1/2" casing.

Perfs:

Top	Bot	Thru	Comments
3337	3340		
3301	3316		
3285	3289		
3220	3226		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4506.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

RECEIVED Form CP-2/3

NOV 01 2010

KCC WICHITA

OCT 25 2010