

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20987-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 29-17S-10W  
1660 feet from S Section Line, 4835 feet from E Section Line  
Lease Name: JANSSEN Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3289 feet

Operator License No.: 7030  
Op Name: JOHN ROY EVANS OIL COMPANY LLC  
Address: 405 FOURTH ST BOX 385  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	301		120 SXS CMT
PROD	5.5	3288	1483	110 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/29/2010 9:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELLING SERVICING INC Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: BRUCE BASYE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/29/2010 11:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3150' AND CAP WITH 5 SX'S CEMENT, CUT CASING @ 1483' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT. PULL CASING TO 950' AND PUMP 35 SXS'S CEMENT. PULL CASING TO 350' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF. TOPPED OFF WITH 5 SX'S CEMENT ON 11-1-2010.

Perfs:

Top	Bot	Thru	Comments
3257	3259	CSG	

RECEIVED  
NOV 04 2010  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-37379

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)