

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-01351-00-00
Spot: SWNE Sec/Twnshp/Rge: 35-30S-2W
4288 feet from S Section Line, 993 feet from E Section Line
Lease Name: FRANTZ Well #: 2
County: SUMNER Total Vertical Depth: 3773 feet

Operator License No.: 31822
Op Name: JOLEN OPERATING COMPANY
Address: 100 N BROADWAY AVE STE 2460
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	448		325 SX
PROD	5.5	3746		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2010 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: PERRY S. HENMAN Company: JOLEN OPERATING COMPANY Phone: (785) 623-8525

Proposed Plugging Method: CIBP OR SAND TO 3700', CAP W/5 SXS. PERF @ 500 CIRC TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/15/2010 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3700', DUMP BAILED 2 SXS CEMENT ON TOP. PRESSURED CASING, HELD OK. SQUEEZE HOLES @ 458'-459', 4 SHOTS. CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 220 SXS 60/40 POZMIX 4% GEL, FOLLOWED BY 70 SXS CLASS A COMMON W/3% CC. CEMENT CIRCULATED. PLUG DOWN 12:00 PM 7-15-2010. CONSOLIDATED CEMENT TICKET #28945.

Perfs:

Top	Bot	Thru	Comments
3746	3773	OH	MISSISSIPPI OPEN

Remarks:
Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN RECEIVED
KANSAS CORPORATION COMMISSION

AUG 09 2010 Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS

✓