

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20461-00-00
Spot: N2SW Sec/Twnshp/Rge: 12-19S-8W
1980 feet from S Section Line, 1320 feet from W Section Line
Lease Name: DOBRINSKI Well #: 1
County: RICE Total Vertical Depth: 1390 feet

Operator License No.: 8917
Op Name: GUSTUS, DEAN DBA JD PRODUCTION
Address: 701 MAIN PO BOX 254
GENESEO, KS 67444

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	211		75 SX
PROD	4.5	1389	887	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2010 9:30 AM
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 07/22/2010 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 1150' AND CAP WITH 4 SX'S CEMENT. CUT CASING AT 887' AND PULL TO 750' AND PUMP 35 SX'S CEMENT. PULL CASING TO 270' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF. USED 120 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
1224	1242	CSG	

Remarks: 60-40 POZ 4% GEL. COPELAND TICKET #C-347884

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
AUG 02 2010
KCC WICHITA

SK