

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23656-00-00
Spot: NESENW Sec/Twnshp/Rge: 7-6S-23W
1650 feet from N Section Line, 2310 feet from W Section Line
Lease Name: SHOEMAKER Well #: 7-1
County: GRAHAM Total Vertical Depth: 3890 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	299		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/02/2010 9:00 PM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: BRAD PARKER Company: H&C OIL OPERATING, INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 08/02/2010 10:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 2125' w/25 sxs.
2nd. Plug at 1350' w/100 sxs.
3rd. Plug at 350' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

RECEIVED
AUG 06 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed CASE MORRIS
(TECHNICIAN)

AUG 03 2010