

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21013-00-00  
Spot: N2SEW Sec/Twnshp/Rge: 11-17S-10W  
3554 feet from S Section Line, 3319 feet from E Section Line  
Lease Name: SNYDER-FREVERT Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3500 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	377		165 SXS CMT
TI	2.875	3059		
PROD	5.5	3113	1675	75 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2010 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/10/2010 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND TO 2900' AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 1675' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT. PULL CASING TO 950' AND PUMP 35 SX'S CEMENT. PULL CASING TO 420' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2996	3000		

Remarks: 60-40 POZ 4% GEL. COPELAND TICKET C-37388

Plugged through: CSG

RECEIVED

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

DEC 02 2010

KCC WICHITA