

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21018-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 11-17S-10W  
3560 feet from S Section Line, 3976 feet from E Section Line  
Lease Name: SNYDER-FREVERT Well #: 2  
County: ELLSWORTH Total Vertical Depth: 3500 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3032		
CIBP	5.5	3140		
SURF	8.625	371		180 SXS CMT
PROD	5.5	3306	2000	160 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/11/2010 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE  
Date/Time Plugging Completed: 11/11/2010 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2900' AND CAP WITH 5 SX'S CEMENT. CUT OFF CASING AT 2000' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT. PULL CASING TO 950' AND PUMP 35 SX'S CEMENT. PULL CASING TO 430' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3250	3254	CSG	
3096	3106	CSG	
2998	3004	CSG	

Remarks: 60-40 POZ, 4% GEL, COPELAND TICKET C-37389

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

RECEIVED

DEC 02 2010

Form CP-2/3

KCC WICHITA