

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23668-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 19-6S-23W  
2310 feet from N Section Line, 330 feet from W Section Line  
Lease Name: STOWELL Well #: 19-1  
County: GRAHAM Total Vertical Depth: 3885 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2010 1:00 AM  
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC  
Proposal Rcvd. from: BRAD Company: H&C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 08/22/2010 2:15 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 2100' w/25 sxs.  
2nd. Plug at 1250' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Case Morris  
(TECHNICIAN)

RECEIVED  
AUG 30 2010  
KCC WICHITA

Form CP-2/3

AUG 26 2010