

TO: ✓  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-073-01096-00-00  
Spot: NWNWSESE Sec/Twnshp/Rge: 27-22S-13E  
1015 feet from S Section Line, 1060 feet from E Section Line  
Lease Name: DUNMAN Well #: 3  
County: GREENWOOD Total Vertical Depth: 1834 feet

Operator License No.: 8093  
Op Name: HAAS, GARY L. DBA GARY HAAS - OI  
Address: 600 ARROWHEAD DR  
NEW STRAWN, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	10	30		WOOD

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2010 8:00 AM  
Plug Co. License No.: 7719 Plug Co. Name: CHEEVER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY L.D. HAAS Company: \_\_\_\_\_ Phone: (620) 364-5893

Proposed Plugging Method: SACKS OF CEMENT AS BOTTOM (1848)- NUMBER OF SACKS TO BE DETERMINED BY KCC REP. CEMENT FOR 250 FT. TO TOP OF SURFACE. ADDITIONAL CEMENT AND PLUGS AS DIRECTED BY KCC.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 08/31/2010 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

LOST CIRC. @ 1145' PUMPED PUMPED 320 BBLS OF DRILLING MUD REGAINED CIRC. FOR 1 JOINT LOST CIRC. AGAIN DECIDED TO SET PLUG @ 1100' MIXED AND PUMPED 50 LBS COTTON SEED HULLS WITH 1600 HUNDRED LBS OF GEL, MIXED 30 SXS CEMENT W/3% CALCIUM, PULLED TUBING UP LET CEMENT SET, TAGGED BOTTOM PLUG TWO HRS LATER PLUG HELD, PULLED TUBING TO 250' PUMPED 265 SXS CEMENT TO SURFACE. PULLED TUBING OUT.

RECEIVED

SEP 13 2010 mH

KCC Chanute Dist. #3

RECEIVED  
SEP 24 2010  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)