

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25179-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 25-18S-24W
1030 feet from S Section Line, 1360 feet from W Section Line
Lease Name: MAIER Well #: 6
County: NESS Total Vertical Depth: 4296 feet

Operator License No.: 8247
Op Name: HEMBREE, ROBERT F
Address: PO BOX 542
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	230		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/11/2010 6:30 AM
Plug Co. License No.: 34432 Plug Co. Name: FALCON DRILLING, LLC
Proposal Rcvd. from: BOB MICKELSON Company: FALCON DRILLING, LLC Phone: (620) 874-0323

Proposed Plugging Method: 1ST PLUG AT 1540' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 11/11/2010 8:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 1540' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

RECEIVED
NOV 19 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SOS.

Plugged through: DP

District: 01

RECEIVED
NOV 12 2010
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)

Form CP5-B