

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20311-00-00
Spot: NWSW Sec/Twnshp/Rge: 22-21S-21W
2141 feet from S Section Line, 4640 feet from E Section Line
Lease Name: SIEVERLING Well #: 1
County: HODGEMAN Total Vertical Depth: 4350 feet

Operator License No.: 8247
Op Name: HEMBREE, ROBERT F
Address: PO BOX 542
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1270		WITH 350 SX CMT
PROD	5.5	4349	500	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2010 9:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: FRED HEMBREE Company: ROBERT F. HEMBREE Phone: (620) 802-7960

Proposed Plugging Method: RUN TBG AS DEEP AS POSSIBLE & PUMP 30 SX CMT WITH 200# HULLS. PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2010 3:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

****CASING LEAK @ 3478' **** RAN TBG TO 3471' & SPOTTED 30 SX CMT. PULLED STRETCH & PARTED PRODUCTION CASING. 1ST PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4278	4286		Mississippian

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
AUG 30 2010
KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

RECEIVED
SEP 07 2010
KCC WICHITA