

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21178-00-00
Spot: NESW Sec/Twnshp/Rge: 4-30S-18W
1986 feet from S Section Line, 3178 feet from E Section Line
Lease Name: SCHMIDT Well #: 2-B
County: KIOWA Total Vertical Depth: 5100 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4750		WITH 2 SX CMT
SURF	8.625	581		WITH 400 SX CMT
PROD	4.5	5093	2200	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/29/2010 8:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4750' & 2 SX CMT. PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2010 10:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 4750' & 2 SX CMT. 1ST PLUG AT 1165' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4828	4832		MARMATON

Remarks: USED 60/40 POZMIX 4% GEL

Plugged through: TBG

District: 01

Signed _____

Jerry W. Stapleton
(TECHNICIAN)

RECEIVED
OCT - 7 2010
KCC DODGE CITY

RECEIVED
OCT 14 2010
KCC WICHITA