

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21054-00-00  
Spot: W2E2NWNW Sec/Twnshp/Rge: 14-29S-18W  
4692 feet from S Section Line, 4488 feet from E Section Line  
Lease Name: UNRUH Well #: 1-B  
County: KIOWA Total Vertical Depth: 4984 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3460		WITH 2 SX CMT
CIBP		4800		WITH 2 SX CMT
SURF	8.629	514		WITH 375 SX CMT
PROD	4.5	4984	0	WITH 500 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/03/2010 9:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L LOEB LLC Phone: (620) 886-2419

Proposed Plugging Method: CIBP ABOVE PERFS & 2 SX CMT. TEST CASING. PERFORATE @ 1100' & CIRCULATE CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/03/2010 1:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG SET CIBP @ 3460' & 2 SX CMT. TEST CASING TO 300 PSI. 2ND PLUG PERFORATED 4 1/2" @ 1100' & PUMPED A TOTAL OF 300 SX CMT. LOST CIRCULATION LATE IN JOB. 3RD PLUG REPAIRED BRADEN HEAD, PUMP 50 SX CMT DOWN 8 5/8" ANNULUS. MAXIMUM PRESSURE 225 PSI. SHUT IN PRESSURE 100 PSI.

Perfs:

Top	Bot	Thru	Comments
4866	4874		MISSISSIPPI
3510	3516		EMPORIA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED  
SEP 22 2010  
KCC DODGE CITY

Signed

*Jerry W. Stapleton*  
PART II

RECEIVED  
(TECHNICIAN)

SEP 27 2010

KCC WICHITA

*[Signature]*  
Form CP-273