

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-199-20125-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 30-15S-42W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: WELSH Well #: 1-30  
County: WALLACE Total Vertical Depth: 5300 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	430	0	w/250 sxs cmt
PROD	5.5	5287	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/07/2010 3:00 PM  
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC  
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB, LLC Phone: (618) 943-2227

Proposed 09/07/2010 - Ordered 150 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Plugging 09/08/2010 - Ordered 450 sxs 60/40 pozmix - 4% gel - 800# hulls - 5 sxs c.c.  
Method: Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/08/2010 1:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 430' w/250 sxs cement.  
5 1/2" production casing set at 5287' w/125 sxs cement.  
TD 5300'. PBTD 5237'.  
Production casing had holes. Production casing fillup to 4200'.  
Perforated production casing at 1750' and 2775'.  
Ran tubing to 4200' - pumped 150 sxs cement mixed with 300# hulls.  
Pulled tubing to 2500' - pumped 35 barrels of water - production casing did not circulate.  
Pulled tubing to 2440'. Shut down until A.M.  
09/08/2010 - Tagged cement at 2961' with tubing.  
Pulled tubing to 2930' - pumped 150 sxs cement - 3% c.c. and 500# hulls.  
Pulled tubing to 1400' - pumped 150 sxs cement - 3% c.c. and 300# hulls.  
Pulled tubing to 700' - pumped 85 sxs cement - cement to surface.  
Pulled tubing to surface. Topped production casing with 25 sxs cement.  
Connected to 8 5/8" surface casing - pumped 40 sxs cement.  
Max. P.S.I. 250#. Casing head ruptured.

Perfs:

Top	Bot	Thru	Comments
5145	5155		

Remarks: ALLIED CEMENTING COMPANY-TICKET #43607 AND #43608.

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

RECEIVED

SEP 20 2010

Form CP-2/3

SEP 10 2010

KCC WICHITA