

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15928-00-01
Spot: SWSE Sec/Twnshp/Rge: 30-20S-13W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MCGREEVY Well #: 1
County: BARTON Total Vertical Depth: 3340 feet

Operator License No.: 31639
Op Name: HERMAN, LEROY DBA DOUBLE L OIL
Address: 801 N US HWY 281
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	12.5	150	0	275 SX
L1	4.5	210		
PROD	7	3230	0	100 SX

Well Type: EOR UIC Docket No: E13421.1 Date/Time to Plug: 09/16/2010 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: DOUBLE L OIL PRODUCERS Phone: (620) 562-8088

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 4% gel.
Well has not been used since 1989 - had casing leak at that time.
Ran tubing into well - found junk in the hole at 1920' - could not get through - decided to plug from there.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 750' - 140'.
Ran tubing to 1900' - tied to tubing and pumped 100 sxs cement.
Pulled tubing to 1500' - pumped 150 sxs cement.
Pulled to 750' - circulated cement with 150 sxs.
Pulled tubing - tied to casing - pumped 120 sxs cement - cement circulated out surface with 120 sxs - shut in.
Topped off with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3230	3321		OPEN HOLE

RECEIVED
SEP 24 2010

KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

SEP 23 2010